

White County, Georgia

ADDENDUM # 1

06/11/19

Setting Up Base and Asphalt Paving on Five County Projects and Leveling w/OGI and Asphalt Overlay on One County Project

White Co. Contract ID:

CP335-909-1(2019)	CP335-402-1(2019)
CP335-932-1(2019)	CP335-134-1(2019)
CP335-057-1(2019)	CP335-910-1(2019)

- Six County Projects bidding collectively but considered as individual projects.

Proposal Closing Date: Friday, June 14, 2019 Time: 1:00 PM

The following questions were asked and answered as shown:

1. Will all parts of the projects require lime or only Yonah Preserve Rd. & Parking, F.M. Rd., and Asa Dorsey Rd.
All of the asphalt as called for in Appendix D1 through D6 shows H-lime is required.
2. Will additional tonnage be added if some driveways and intersecting roads require more mix to tie-in properly?
The additional tonnage has already been calculated and included in the tonnage for the line items in Appendix D1 through D6. If we have made an error in calculation additional tonnage may be added with the White County Project Manager's approval.
3. Is the contractor required to bid all six projects or can the contractor choose which projects they wish to bid?
The contractor is required to bid all six projects and be prepared to be responsible for the work in all six.
4. In Appendix D1-7, the table includes a column for 'Unit Price' however, this column is being used to specify the units for the quantities. Does the county want a unit price included in the bid sheet? If so will a revised bid sheet be issued to accommodate this? We mistakenly removed a column and Yes a Unit Price is needed and an Addendum with revisions for Appendix D1-D6 to include the missing column appears in this addendum.
5. On roads requiring base setup, is the contractor responsible for any shoulder grading that may be necessary?
There should be no grading required on the shoulders. White County will have the base installed in place and the Contractor will be required to set/compact the base to prepare it for prime and paving in accordance with Section 317 of the GDOT specs. White County will build the shoulders on all the roads after paving is complete.

Bids not signed shall be declared as “Non-Responsive” and may not be considered for award.

**APPENDIX D1
BID PRICING**

**Setting of Base and Asphalt Paving
Fire Station #6
White County Contract ID: CP335-909-1(2019)
Fire Station #6 – 1198 Sq.Yds.
Project begins: Hwy. 129 N. Project ends: Hwy. 129 N.**

Bid Line Number	Pay – Item	Description	Unit	Est. Units	Unit Price	Bid Amount
0005	317-6000	Preparation of base	SY	1198		
0010	412-1000	Bituminous Prime	GL	300		
0015	402-3190	Recycl Asph Conc 19mm SuperPave Gp1 or 2 Incl Bitum Mat'l & H-lime @220lbs/SY	TN	115		
0020	413-1000	Bitum Tack Coat	GL	60		
0025	402-3101	Recycled AsphConc 9.5 Superpave, Type I Blend I, incl bituminous mat'l & H-lime @110lbs/SY	TN	66		
TOTAL BID AMOUNT					→	

NAME & TITLE OF PERSON AUTHORIZED TO SIGN

Name (Print)

SIGNATURE

TITLE

Bids not signed shall be declared as “Non-Responsive” and may not be considered for award.

**APPENDIX D2
BID PRICING**

**Setting of Base and Asphalt Paving
of Shepherd Dr. – CR402
White County Contract ID: CP335-402-1(2019)
Shepherd Dr. – .18mi – 951lf – 20ft paved width
Project begins: Appalachian Pkwy. Project ends: Claude Sims Rd.**

Bid Line Number	Pay – Item	Description	Unit	Est. Units	Unit Price	Bid Amount
0005	317-6000	Preparation of base	SY	2219		
0010	412.1000	Bituminous Prime	GL	528		
0015	402-3190	Recycl Asph Conc 19mm SuperPave Gp1 or 2 Incl Bitum Mat'l & H-lime @220lbs /SY	TN	257		
0020	413-1000	Bitum Tack Coat	GL	110		
0025	402-3101	Recycled AsphConc 9.5 Superpave, Type I Blend I, incl bituminous mat'l & H-lime @165lbs/SY	TN	261		
TOTAL BID AMOUNT					→	

NAME & TITLE OF PERSON AUTHORIZED TO SIGN

Name (Print)

SIGNATURE

TITLE

Bids not signed shall be declared as “Non-Responsive” and may not be considered for award.

**APPENDIX D3
BID PRICING**

**Setting of Base and Asphalt Paving
of Asa Dorsey Rd. – CR932
White County Contract ID: CP335-932-1(2019)
Asa Dorsey Rd. – .26mi – 1349lf – 18ft paved width
Project begins: Hwy. 254 Project ends: 621 Asa Dorsey Rd.**

Bid Line Number	Pay – Item	Description	Unit	Est. Units	Unit Price	Bid Amount
0005	317-6000	Preparation of base	SY	2848		
0010	412.1000	Bituminous Prime @ .25 gal/SY	GL	675		
0015	402-3101	Recycled AsphConc 9.5 Superpave, Type I Blend I, incl bituminous mat'l & H-lime (220lbs/SY)	TN	320		
TOTAL BID AMOUNT					→	

NAME & TITLE OF PERSON AUTHORIZED TO SIGN

Name (Print)

SIGNATURE

TITLE

Bids not signed shall be declared as “Non-Responsive” and may not be considered for award.

**APPENDIX D4
BID PRICING**

**Setting of Base and Asphalt Paving
of F.M. Rd. - CR134
White County Contract ID: CP335-134-1(2019)
F.M. Rd. - .35mi - 1848lf - 16ft paved width
Project begins: Kellum Valley Rd. Project ends: Harkins Rd.**

Bid Line Number	Pay – Item	Description	Unit	Est. Units	Unit Price	Bid Amount
0005	317-6000	Preparation of base	SY	3460		
0010	412.1000	Bituminous Prime @.25 gal/SY	GL	830		
0015	402-3101	Recycled AsphConc 9.5 Superpave, Type I Blend I, incl bituminous mat'l & H-lime (220lbs/SY)	TN	410		
TOTAL BID AMOUNT					→	

NAME & TITLE OF PERSON AUTHORIZED TO SIGN

Name (Print)

SIGNATURE

Bids not signed shall be declared as “Non-Responsive” and may not be considered for award.

**APPENDIX D5
BID PRICING**

**Level w/OGI and Overlay w/9.5 Superpave
for Old Blue Creek Rd. – CR057
White County Contract ID: CP335-057-1(2019)
Part 1 19ft x 1907 ft
Part 2 18ft x 179 ft
Part 3 16ft x 1111 ft
Part 4 18ft x 12 ft
Part 5 12ft x 156 ft**

.637mi – 3365lf – 12-19ft paved width varies

Project begins: Cleveland City Limits Project ends: Laceola Entrance

Bid Line Number	Pay – Item	Description	Unit	Est. Units	Unit Price	Bid Amount
0005	415-5000	Asphaltic concrete open graded crack relief interlayer, GP 2 only, incl bitum mat'l & H-lime @ 110lbs/SY	TN	365		
0010	413.1000	Bituminous Tack Coat CRS2H or Blacklidge Ultra Tack, or RC70 or MC70 @.05gl per SY	GL	660		
0015	402-3101	Recycled AsphConc 9.5 Superpave, Type I Blend I, incl bituminous mat'l & H-lime @ 165lbs/SY	TN	590		
TOTAL BID AMOUNT					→	

NAME & TITLE OF PERSON AUTHORIZED TO SIGN

Name (Print)

SIGNATURE

Bids not signed shall be declared as “Non-Responsive” and may not be considered for award.

**APPENDIX D6
BID PRICING**

**Setting of Base and Asphalt Paving
of Yonah Preserve – CR910
White County Contract ID: CP335-910-1(2019)
Yonah Preserve – Road into park and parking lot**

Bid Line Number	Pay – Item	Description	Unit	Est. Units	Unit Price	Bid Amount
0005	317-6000	Preparation of base	SY	3901		
0010	412.1000	Bituminous Prime @ .25 gal per SY	GL	976		
0015	402-3101	Recycled AsphConc 9.5 Superpave, Type I Blend I, incl bituminous mat'l & H-lime (220lbs/SY)	TN	430		
0020	652-0000	Striping of Parking Lot (includes Handicap Emblems & Loading Marks)	LS	1		
TOTAL BID AMOUNT					→	

NAME & TITLE OF PERSON AUTHORIZED TO SIGN

Name (Print)

SIGNATURE

APPENDIX D7

BID PRICING GRAND TOTAL SHEET

Please add all six project totals together and place grand total on this sheet.

WHITE CO. CONTRACT ID'S:

CP335-909-1(2019)	CP335-402-1(2019)
CP335-932-1(2019)	CP335-134-1(2019)
CP335-057-1(2019)	CP335-910-1(2019)

- Six projects bidding collectively but considered as individual projects.

Grand Total for:

Setting Up Base and Asphalt Paving on Five County Projects and
Leveling w/OGI and Asphalt Overlay on One County Project

Total Bid Amount: _____

NAME & TITLE OF PERSON AUTHORIZED TO SIGN

Name (Print)

SIGNATURE

TITLE

Note: A signed acknowledgement of this addendum must be received by the White Co. Road Dept. and attached to your bid response. This addendum is part of the contract.

Vendor Name: _____

Address: _____

Email: _____

Authorized Signature: _____ Date: _____

Name (Printed): _____ Title: _____

End of Addendum #1.